EXHIBIT A.9 BID ANALYSIS, QUOTES & BACKUP

Construction Manager at Risk for Pima County Regional Wastewater Reclamation Department - North Rillito Interceptor Rehabilitation Project No. 3NRI14

See the following attached bids and quotes from material suppliers, vendors, etc.:



SUBCONTRACTOR BID FORM - 10.10,2014 Revision

Office: 520-207-8228 | Fex 629-592-9761 1904 W. Prince Rd., Tucson, AZ 85705 www.bfcontracting.com | License # AZ ROC-039744

To:	B&F Contracting, Inc.
From:	Insituform Technologies, LLC
	17988 Edison Ave, Chesterfield, MO 63005
Phone:	636.530.8000
Email:	dcarroll@insituform.com
RE:	Construction Manager at Risk Services for North Rillito Interceptor Rehabilitation

Subject: Bld Due Date:

Monday 10/13/2014

Time:

3:00 PM

Location:

Pima County Project No. 3NRI14

B&FTucson Office

1904 W. Prince Rd., Tucson, AZ

General Information:

B&F Contracting, Inc., acting as the CM@Risk Contractor is requesting proposals from approved contractors interested in furnishing subcontractor services for the project.

Plan Availability:

Electronic Copies of Project drawings and Specifications will be available for pickup at the B&F Tucson Office

**Blds will be received and opened privately by B&F with PCRWRD

1 Special Instructions to Bidders

- 1.01 Instruction to Bidders are provided for the purpose of clarifying the Subcontractor Bid Form. Each prospective Bidder shall review the below instructions and all documents prior to submission of their respective bid.
- 1.02 If prospective bidder elects not to bid, please inform B&F Contracting Inc. in writing immediately via fax or email.
- 1.03 Bids can be submitted electronically (dfoley@bfcontracting or tomf@bfcontracting.com), fax (623.582.3761) or hand delivered at the B&F Tucson Office by 3:00 PM Arizona time Monday October 13, 2014, located at 1904 W. Prince Rd., Tucson, AZ.
- 1.04 Any bids received after 3:00 PM on October 13, 2014 will be considered non-responsive and not be read at the bid opening.
 Telephone bids will not be accepted, email or fax bids are acceptable. Fax bids will be sent to 623.582.3761
 If the bidding contractor elects to fox or email their bidbid it will be their responsibility to call and confirm receipt of your faxed or emailed bid before the bid due time.
- 1.05 Any and all questions related to this bid shall be directed in writing via email to Dan Foley at the email addresses listed above.
 The last day for questions to be answered will be Friday October 3, 2014
- 1.06 Bids are required to be submitted on the 'Subcontractor Bid Form'. Please Insert N/A on bid items outside your scope.
- 1.07 Receipt and review of Addenda and/or Amendments shall be acknowledged by the Bidders on their completed Subcontractor Bid Form
- 1.08 B&F to provide electronic copies of plans, specifications, as-builts, pre-videos, inspection reports, etc., to bidding contractors on usb flash drive. Bidding contractors to return flash drives after bid period is complete.
- 1.09 Pima County Regional Wastewater Reclamation Department and B&F Contracting reserve the right to accept or reject any and/or all Bids.
- 1.1 Pima County Regional Wastewater Reclamation Department and 8&F Contracting reserve the right to waive any informality in any Bid.
- 1.11 Prospective bidders are to refrain from contacting the Owner or Designer with questions regarding the Bid. All questions are to be directed to B&F Contracting, Inc.
- 1.12 Bids received after the bid due date/time will not be considered. Any bid modification received after the bid date/time will not be considered.
- 1.13 Contractor selection criteria for the rebabilitation work will be based on the following criteria; Price, Qualifications and Schedule.

- 1.14 The bidder assumes full responsibility for timely delivery at the location specified for receipt of bids.
- 1.15 Bids which modify any of the provisions of the Bidding or Contract documents will not be considered.
- 1.16 A Bid that is in the possession of B&F Contracting Inc. may be withdrawn by the bidder up to the time of the bid opening.
- 1.17 Each Bidder shall provide unit prices in accordance with the required Bid Schedule
- 1.18 Bid pricing shall include but is not limited to the following: Any and all costs for fabrication, delivery and expeditious delivery, layout, supervision, labor, materials, equipment, uncrating, setting, hoisting, installation, parking, storage, insurance, permits, engineering, supervision tools, payroll taxes, escalation, overhead, profit, shop drawings, submittals, samples, mock ups, overtime or weekend work and any other costs necessary to complete the work required in accordance with all associated project documents per the provided construction schedule.
- 1.19 Bid prices shall be based on earliest attainable delivery without incurring additional costs to the owner.
- 1.20 The successful Bidder will be notified only after a thorough review and evaluation of all the bids that have been made to the PCRWRD and B&F Contracting. Bid evaluations will based on but not limited to: Scope, price qualifications and ability to meet the construction schedule. A post bid interview may also be required.
- 1.21 CIPP Lining Contractors are required to submit CIPP shot schedule with bid documents. Failure to submit CIPP shot schedule with the bid documents will result in the rejection of your bid proposal. Please include Reach i.D., Length, Thickness, Inversion/Tail MH's, Etc.
- 1.22 Each bidder shall include overtime rates/pricing into their bid. This project will have a 24/7 schedule with 7-day work weeks to meet the construction schedule provided with the bid documents. B&F will not accept additional costs for overtime rates.
- 1.23 CIPP & Manhole Contractors are to submit crew availability and quantities to B&F Contracting with their bid. A Microsoft Word document will be acceptable.
- 1.24 CIPP Lining & MiH Rehab Contractors are to commit and maintain a single, consistent crew and foreman for each of the phases.

 The interchanging of crew and personnel from phase to phase will not be accepted on this project.
- 1.25 CIPP & Manhole Contractors are to submit a list including key personnel on the project (Superintendent & Project Manager) to 8&F Contracting Inc. for review with the bid documents.
- 1.26 CIPP & Manhole Contractors are to submit a list showing your current workload in the Southwest Region, where crews specific to AZ are currently being utilized. Please list project name, size, schedule and crew commitments.
- 1.27 No more than 1 major intersection may be blocked at a time by either the CIPP, Manhole Rehab or Bypass Pumping contractor.
- 1.28 CIPP Lining contractors are to refrain and/or limit inversion in private properties where access is limited (i.e. backyard, driveway, landscaped areas)

 All manholes residing in these areas will need to be used as "Tail Manholes" or "Thru Manholes" for the liner.
- 1.29 Bypass Pumping for the NRI sewer flows and all incoming lateral flows will be handled by B&F Contracting. Please do not include these costs in your bid.
- 1.30 Manhole Rehab Contractor to provide and place their own plugs as required to complete their own scope of work, and to maintain a dry work environment.
- 1.31 It is B&F Contracting's intent to award the CIPP lining contract for the entire project to one (1) Contractor
- 1.32 Manhole Rehabilitation Contractor to verify that their product is on the PCRWRD's Approved Product List.
- 1.33 The MH Coating/Rehab work could possibly be split between two (2) contractors due to SBE/DBE Compliance with Pima County Procurement.
- 1.34 Temperature sensor cable to continuously monitor the cure temperature of CIPP liner along the entire length of pipe, to be provided by the CIPP contractor
- 1.35 MH Coating to provide sandbagging or plugging for nuisance water during all MH underlayment and Coating operations at each individual MH. 8&F to provide all mainline flow management for 8-inch and larger flows, but cannot guarantee a completely dry manhole condition.
- 1.36 CIPP & Manhole Coating Contractors are required to field verify existing conditions of sewer and manhole diameters prior to bidding this project. It is expected that any variation from the B&F provided bid schedule be included within your unit cost. It is up to the bidding contractor to confirm existing sizes of the interceptor and manholes, and cross reference with the Pima County GIS System, As-Builts and MH inspection Reports.
- 1.37 Manhole Coating Rehabilitation work includes, but is not limited to: Surface Preparation Work, Build-Back, Re-Work of Invert and/or Channels, Chipping, Demolition Re-Profiling and Corrosion Resistant Coatings as called out on the Manhole Inspection Report provided on the USB drive. Please pay attention to Brown & Caldwell's specific recommendations for repair at each manhole and include them with your VF pricing.
- 1.38 Please provide a list of your current workload in Arizona, Nevada and California with the assigned key personnel managing those projects.
- 1.39 B&F will require full time supervision from the MH Coating and CIPP Lining Contractors. It is a requirement to provide full time onsite supervision throughout the course of this project.

- 1.40 A pre-liner is required for CIPP Lining of existing Coated ACP sewer lines. B&F has provided initial quantities below on the bid schedule but the CIPP contractor is tasked with field verifying those quantities.
- 1.41 CIPP Lining & MH Coating Contractors are required to provide a Payment/Performance Bond on this project per Item 12 below. Please include this cost under under the 'Bond' section of this bid for consideration (do not include in your unit cost).
- 1,42 Water Cure is the only acceptable curing/inversion method on this project. Air/Steam will not be accepted and is grounds for disqualification if included in your bid.
- 1.43 MH Rehabilitation/Coating Contractor to provide five (5) year warranty bond with their bid. Contractor to provide breakout pricing for this cost on the bottom of the bid schedule below (not in the VF unit pricing).
- 1.44 Lining Contractors to provide all styrene monitoring per the RWRD Specifications.
- 1.45 B&F to provide all new manhole frame/covers and concrete collars.
- 1.46 MH rehabilitation/Coating Contractor to pay close attention to new MH Coatings Specifications provided for this project. This specification is brand new for the county and has not been used in the past. Please review the revised cleaning, underlayment, finish and testing requirements outlined.
- 1.47 CIPP Lining Contractors are not to include costs for cleaning, pre and post video in your unit prices. B&F to provide. B&F expects the CIPP Lining Contractor to take part in the coordination and scheduling process for the clean/cctv subcontractor.
- 1.48 MH Coating Contractor to provide costs for removal of existing steps and replacement with new in their VF unit pricing on the bid schedule below.
- 1.49 MH Coating Contractor to remove any T-Lock as necessary at existing manholes.
- 1.50 CIPP Lining Contractor to provide all 'End Seals' using Neopoxy or similar product to complete their own scope of work
- 1.51 MIH Coating Contractor scope of work includes coating of the invert to match the thickness of the CIPP Lining. Also include costs for coating and Tie-In to CIPP liner at "Lined Through Manholes" and "Tail End" with compatible product.
- 1.52 CIPP Lining contractor to provide their own construction water for CIPP lining operations, including, but not limited to; hydrant meters, piping, valves permits, water ramps, etc.. If any trenching is required for roadway crossings, please provide the areas and dimensions on an extra sheet with your bid.
- 1.53 CIPP Lining contractor to furnish and install hydrophilic seals between the host pipe and new CIPP Liner at each manhole.
- 1.54 MH 8716-04 to 8716-03 in Phase 1 has been previously CIPP lined on a recent project. Please do not include CIPP costs for this reach.
- 1.55 MH Coating contractor to review Sabino Creek Siphon Inlet & Outlet Structure As-built Drawings for rehabilitation and coating work at 4466-IN & 4466-OUT.
 Work scope Includes, but is not limited to, cleaning, coating and new redwood diversion stop logs. B&F remove and replace existing concrete lids with new precast material that will need to be coated.
- 1.56 CIPP & MH Coating Contractors are to provide daily cleanup of the Jobsite and manholes/reaches. It is expected for MH Contractors to cleanup all debris generated from cleaning, preparation and coating activities.
- 1.57 CIPP & MH Coating Contractor to provide a letter from your bonding company that you have the capacity to provide a payment/performance bond for this project.
- 1.58 Bidding Contractors to adhere to Pima County, 2012 Engineering Design Standards and Standard Specifications and Details for Construction 2012

2 Mandatory Pre-Bid Meeting

A Mandatory Pre-Bid Conference has been scheduled for 9/30/2014 at 10:00 am and will be held at the PCRWRD Conveyance Office located at 3355 N. Dodge Bivd., Tucson, AZ

3 Project Schedule:

Bid Documents available to Subcontractors 29-Sep-14
Mandatory Pre-Bid Meeting 30-Sep-14
Final Day for Questions 3-Oct-14
Bid Due Date 13-Oct-14

Bid Review October 13 through October 17

Subcontractor Notification of Selection 17-Oct-14
Submitted Due Date 29-Oct-14
Notice to Proceed 5-Novi-14

4 North Rillito Interceptor - As-Builts

Electronic copies have been made available for the as-builts associated with the NRI Rehab Project. Please review these to verify shot lengths, dimensions, manhole sizes, structures, pipe materials and interior diameter prior to the bid and ordering of materials.

5 North Rillito Interceptor - Manhole Inspection Report

Electronic copies of the manhole inspection report have been made available to all potential MH & CIPP contractors prior to the bid. Please pay particular attention to the notes and photos of the manholes in regards to the condition of the existing channels and benches. The costs for rehabilitating these will need to be included in your VF price for manhole rehabilitation.





6 Flow Management Plans - Phase 1, 2, & 5

8&F will make available electronic copies of our flow management plans for Phase 1, 2 & 5, as they have been developed and approved at this point. The limits of Phases 3, 4 & 6 will be shown on a conceptual map. Phase 3 is tentatively from Sabino Canyon Rd. to Craycroft. Phase 4 Craycroft to Swan. Phase 6 is from Alvernon Way to Campbell Rd.

7 Project Sequence & Scheduling

This project will be broken into six (6) separate Rehabilitation Phases along the Rillito River. With the anticipation of each phase lasting 3-4 months for all rehabilitation and repair type work (New MH's, CIPP, Structures, Point Repairs, etc.). It is anticipated that there will be lags between each phases of roughly one (1) month to allow for the FMP installation, where there will be no CIPP or MH Rehab work taking place. See below for the phase limits:

- Phase 1 Woodland Rd. to the Sabino Creek
- Phase 2 Sabino Creek to 800' west of Sabino Canyon Rd.
- Phase 3 Sabino Canyon Rd. to Craycroft Rd.
- Phase 4 Craycroft Rd. to Swan Rd.
- Phase 5 Swan Rd. to Alvemon
- Phase 6 Alvernon to Campbell Rd.

Phase 1 Rehabilitation Section

This section encompasses the CIPP lining and Manhole Rehab work from (MH's 8716-20 to SIPHON 4466-IN). Approximately from Woodland Rd. to west of Tanque Verde Rd. ending at the Sabino Creek

Phase 2 Rehabilitation Section

This phase encompasses the CIPP Uning and Manhole Rehab work from MH's (4466-OUT to 1700-04). Approximately from the Sabino Creek to just west of Sabino Canyon Rd.

Phase 3 Rehabilitation Section

This phase encompasses the CIPP lining and Manhole Rehab work from MH's (1700-04 to 5033-03). Approximately from west of SabIno Canyon Road to just west of Craycroft Rd.

Phase 4 Rehabilitation Section

This phase encompasses the CIPP Lining and Manhole Rehab work from MH's (5033-03 to 1712-01). Approximately from west of Craycroft Rd. to east of Swan Rd.

Phase 5 Rehabilitation Section

This phase encompasses the CIPP Lining and Manhole Rehab work from MH's (1712-01 to 1710-05). Approximately from east of Swan Rd. to Alvernon Way.

Phase 6 Rehabilitation Section

This phase encompasses the CIPP Lining and Manhole Rehab work from MH's (1710-05 to 8809-01). Approximately from Alvernon Way to west of Campbell Rd.

8 Bid Schedule

m Number & Description	Pipe Material	Quantity	Unit	Unit Price	Total
P UNING REHABILITATION - PHASE 1	•				
1 Mobilization		1	LS	12,800.00	12,900.00
2 15" CIPP Lining (MH 8716-20 to 8716-10)	Coated ACP	5,100	LF	31.70 14	1,670.0
3 15" Pre-Liner for CIPP Lining	Coated ACP	5,100	LF	3.90	19,890.00
4 18" CIPP Lining (MH 8716-10 to MH 8716-02	Coated ACP	3,009	l.F	42.80 12	38,785.
5 18" Pre-Liner for CIPP Lining	Coated ACP	3,009	Ŀ	4.50	3,540.
6 24" CIPP Lining (MH 8716-02 to 4466-IN)	VCP	416	LF	76.00 3	31,616.0
		sui	STOTAL - CII	PP LINING REHABILITATION	68,401
ANHOLE REHABILITATION & COATING - PHASE 1				-	
					
1 Rehabilitate & Coat Existing Manholes		181	VF	1	
Rehabilitate & Coat Existing Base for MH Str 2 (MH 8716-05 & 8716-04)	uctural Inserts	2	EA		
Coat New CIP MH Base for 72° Manhole Rer 3 (MH 8716-07, 8716-06, 8716-03)	noval/Replacement	3	EA		
Specification Item E.3.1 - Efforts for cosmetic irregularity free uniform finish, free from trade depressions, ripples, waves, bubbles, bumps coating layer using an approved repair methorofile for coating.	120	HR			
1-inch additional underlayment application	for extremely				
5 deteriorated manholes		45	VF	L	
		SUBTOT	AL - MH REI	HABILITATION & COATINGS	
	**	Please List You	r Installatio	n Days Required to Complete You	r Own Scope of Work (C
			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		7
				CIPP Lining	
				MH Coatings	
	Please List	any MH's That	Require CIP	P Inversion Access, Cone/Barrel Ro	emovals or Base Modifi
See	attacs	red .	SOU	eadsherts	

В.	Phase 2 Rehabilitation Section - Sabino Cre	ek Siphon to Sa	bino Creek I	Road (4466-	OUT to 1700-04)	
Item N	umber & Description	Pipe Material	Quantity	Unit	Unit Price	Total
<u>CIPP LI</u>	NING REHABILITATION - PHASE 2					
1	Mobilization		1	LS	12,900.00	12,900.00
2	21" CIPP Lining (1811-01A to MH 1700-16)	Coated ACP	278	LF	72.70	20,210.60
3	21" Pre-Liner for CIPP Lining	Coated ACP	278	LF	5.30	1473.40
4	24° CIPP Lining (4466-OUT to 1811-01A)	VCP	155	LF	110.80	17,174.00
5	27" CIPP Lining (1700-16 to 1700-15 & 6295-01 to 1700-04)	Coated ACP	5,304	LF	15.20	398,860.80
6	27" Pre-Liner for CIPP Lining	Coated ACP	5,304	LF	5.30	28,111.20
7	27" CIPP Lining (1700-15 to 6295-01)	VCP	852	LF	75.20	64,870.40
			S	JBTOTAL - CIP	P LINING REHABILITATION	542,800,40
MANH	OLE REHABILITATION & COATING - PHASE 2					., -
1	Rehabilitate & Coat Existing Manholes		160	VF		
2	Rehabilitate & Coat Existing Base for MH Structural 12)	insert (MH 1700-	1	EA		
3	Coat New CIP MH Base for 60" Manhole Removal/F (MH 1700-07)	eplacement	1	EA		
4	Coat New CIP MH Base for 84" Manhole Removal/F (MH 1700-15, 6295-01, 1700-11, 1700-09, 1700-08)		5	EA		
5	Specification Item E.3.1 - Efforts for cosmetic finish irregularity free uniform finish, free from trowel madepressions, ripples, waves, bubbles, bumps or cracoating layer using an approved repair method. To profile for coating.	rks, voids, king in the final	96	, HR		
6	1-inch additional underlayment application for extr deteriorated manholes	emely	44	VF		
			SUBTO	TAL - MH REH	IABILITATION & COATINGS	
		**	Please Hist Vo	ur Installation	n Days Required to Complete	: Your Own Scope of Work (Calendar Days):
			- /	,	CIPP Lining	OF
					MH Coatings	,
		SANI	NALIJA -1	A Bassales Cine	O laurendam decesso Commission	mal Barracula na Daga Madifisahi 2-1
			any MH's Tha		r inversion Access, Cone/Bai	rel Removals or Base Modifications Below:
		See a	nai	ned		

C. Phase 3 Rehabilitation Section - Sabino Canyon Rd. to Craycroft Rd (MH 1700-04 to 5033-03)											
imber & Description	Pipe Material	Quantity	Unit	Unit Price	Total						
NING REHABILITATION - PHASE 3											
Mobilization		1	LS	12,900.00	12,900.00						
27" CIPP Lining (MH 1700-04 to MH 1714-12)	Coated ACP	1,857	LF	77.90	144,660.30						
1714-12)	Coated ACP	1,857	LF	5.30	9842.18						
MH 1714-07 to MH 5033-03)	Unlined RCP	7,938	LF	84.50	670,761.00						
30" CIPP Lining (MH 1714-08 to MH 1714-07)	VCP	883	LF	81.80	72, 229.40						
		şu	BTOTAL-CIF	P LINING REHABILITATION	910,392.80						
DLE REHABILITATION & COATING - PHASE 3				r							
Rehabilitate & Coat Existing Manholes		423	VF								
irregularity free uniform finish, free from trowel madepressions, ripples, waves, bubbles, bumps or crack	rks, voids, king in the final	184	HR								
1-inch additional underlayment application for extra deteriorated manholes	emaly	105	VF								
		SUBTOT	AL - MH REI	ABILITATION & COATINGS							
**Please List Your Installation Days Required to Complete Your Own Scope of Work (Calendar Days):											
				MH Coatings							
				_							
	_	•	Require CIPI	Pinversion Access, Cone/Bar	rel Removals or Base Modifications Below:						
	Mobilization 27° CIPP Lining (MH 1700-04 to MH 1714-12) 27° Pre-Liner for CIPP Lining (MH 1700-04 to MH 1714-12) 30° CIPP Lining (MH 1714-12 to MH 1714-08 and MH 1714-07 to MH 5033-03) 30° CIPP Lining (MH 1714-08 to MH 1714-07) DIE REHABILITATION & COATING - PHASE 3 Rehabilitate & Coat Existing Manholes Specification Item E.3.i - Efforts for cosmetic finish to irregularity free uniform finish, free from trowel me depressions, ripples, waves, bubbles, bumps or craccoating layer using an approved repair method. To profile for coating.	Mobilization 27° CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 27° Pre-Liner for CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 30° CIPP Lining (MH 1714-12 to MH 1714-08 and MH 1714-07 to MH 5033-03) Unlined RCP 30° CIPP Lining (MH 1714-08 to MH 1714-07) VCP DEE REHABILITATION & COATING - PHASE 3 Rehabilitate & Coat Existing Manholes Specification Item E.3.i - Efforts for cosmetic finish work to provide irregularity free uniform finish, free from trowel marks, voids, depressions, ripples, waves, bubbles, bumps or cracking in the final coating layer using an approved repair method. To provide uniform profile for coating. 1-inch additional underlayment application for extremely deteriorated manholes	Mobilization 1 27" CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 1,857 27" Pre-Uner for CIPF Lining (MH 1700-04 to MH 1714-12) Coated ACP 1,857 30" CIPP Lining (MH 1714-12 to MH 1714-08 and MH 1714-07 to MH 5033-03) Unlined RCP 7,938 30" CIPP Lining (MH 1714-08 to MH 1714-07) VCP 883 SUIDE REHABILITATION & COATING - PHASE 3 Rehabilitate & Coat Existing Manholes 423 Specification Item E.3.i - Efforts for cosmetic finish work to provide Irregularity free uniform finish, free from trowel marks, voids, depressions, ripples, waves, bubbles, bumps or cracking in the final coating layer using an approved repair method. To provide uniform profile for coating. 184 1-inch additional underlayment application for extremely deteriorated manholes 106	Mobilization 1 LS 27° CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 1,857 LF 27° Pre-Uner for CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 1,857 LF 30° CIPP Lining (MH 1714-12 to MH 1714-08 and MH 1714-07 to MH 5033-03) Unlined RCP 7,938 LF 30° CIPP Lining (MH 1714-08 to MH 1714-07) VCP 883 LF SUBTOTAL - CIP SUBTOTAL - CIP SUBTOTAL - CIP SPECIFICATION & COATING - PHASE 3 Rehabilitate & Coat Existing Manholes 423 VF Specification Item E.3.i - Efforts for cosmetic finish work to provide irregularity free uniform finish, free from trowel marks, voids, depressions, ripples, waves, bubbles, bumps or cracking in the final coating layer using an approved repair method. To provide uniform profile for coating. 184 HR 1-inch additional underlayment application for extremely deteriorated manholes **Please List any MH's That Require CIPI **Please List any MH's That Require CIPI	INTER REHABILITATION - PHASE 3 Mobilitzation 1 LS 2, 900, 00 27" CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 1,857 LF 77, 90 27" Pre-Uner for CIPP Lining (MH 1700-04 to MH 1714-12) Coated ACP 1,857 LF 5,-30 30" CIPP Lining (MH 1714-12 to MH 1714-08 and MH 1714-12) to MH 1714-08 and MH 1714-07 to MH 5033-03) Unlined RCP 7,938 LF 84.50 SUBTOTAL - CIPP Lining (MH 1714-08 to MH 1714-07) VCP 883 LF 81.50 SUBTOTAL - CIPP Lining REHABILITATION & COATING - PHASE 3 Rehabilitate & Coat Existing Manholes 423 VF Specification item E.3.i - Efforts for cosmetic finish work to provide irregularity free uniform finish, free from trowel marks, voids, depressions, ripples, waves, bubbles, bumps or cracking in the final coating layer using an approved repair method. To provide uniform profile for coating. 184 HR 1-inch additional underlayment application for extremely deteriorated manholes 105 VF SUBTOTAL - MH REHABILITATION & COATINGS **Please List Your Installation Days Required to Complete CIPP Lining MH Coatings MM Coatings **Please List any MM's That Require CIPP Inversion Access, Cone/Bar						

D.	D. Phase 4 Rehabilitation Section - Craycroft Rd to Swan Rd (IMH 5033-03 to 1712-01)										
Item N	umber & Description	Pipe Material	Quantity	Unit	Unit Price	Total					
CIPP LI	NING REHABILITATION - PHASE 4										
1	Mobilization		1	LS	12,900.00	12,900.00					
2	30" CIPP Lining (MH 5033-03 to MH 1712-06)	Unlined RCP	2,681	LF	91.80	246,115.80					
3	33° CIPP Lining (MH 1712-06 to MH 1712-01)	Unlined RCP	2,761	ĹF	95.70	264,221.70					
			SU	BTOTAL - CIF	P LINING REHABILITATION	523,243.50					
MANH	OLE REHABILITATION & COATING - PHASE 4										
1	Rehabilitate & Coat Existing Manholes		141	VF							
2	Specification Item E.3.1 - Efforts for cosmetic finish work to provide irregularity free uniform finish, free from trowel marks, voids, depressions, ripples, waves, bubbles, bumps or cracking in the final coating layer using an approved repair method. To provide uniform										
1	profile for coating.		80	HR							
, з	1-inch additional underlayment application for ex- deteriorated manholes	tremely	36	VF							
:			SUBTO	FAL - MH REI	ABILITATION & COATINGS	tinantamana and an analysis an					
		••	Please List Yo	ır installatlo	n Days Required to Complet	e Your Own Scope of Work (Calendar Days):					
					CIPP Lining	8,					
					MH Coating	\$					
		◆◆Please List	any MH's That	: Require CIP	P Inversion Access, Cone/Ba	rrel Removals or Base Modifications Below:					
		Sec	- at	tal	led						

tem N	umber & Description	Pipe Material	Quantity	Unit	Unit Price	Total
IPP LI	NING REHABILITATION - PHASE 5					
1	Mobilization		1	ıs	12,900.00	12,900.00
2	33" CIPP Lining (MH 1712-01 to MH 1710-05)	Unlined RCP	5,383	LF	111.10	598,051.30
			s	UBTOTAL - CIP	P LINING REHADILITATION	610,951.30
VANH	OLE REHABILITATION & COATING - PHASE 5					
1	Rehabilitate Existing Sewer Manholes		220	VF		
2	Specification item E.3.1 - Efforts for cosmetic finish irregularity free uniform finish, free from trowel m depressions, rippies, waves, bubbles, bumps or cra- coating layer using an approved repair method. To	arks, voids, acking in the final				
	profile for coating.		80	HR		
3	1-inch additional underlayment application for ext deteriorated manholes	remely	55	VF		
			SUBTO	TAL - MH REH	IABILITATION & COATINGS	
		**	Piease List Yo	our Installation	n Days Required to Complete	Your Own Scope of Work (Calendar Days):
					CIFF GRING	
			CIPP Te	st Section Lab	Test Result Turnaround Time	<u> </u>
					MH Coatings	
	,	**Please List	any MH's Tha	it Require CIPI	Inversion Access, Cone/Bar	rei Removals or Base Modifications Belova
		See	07	Hack	hed	
				e e e e e e e e e e e e e e e e e e e		

F Item N	Phase 6 Rehabilitation Section - River and A lumber & Description	Pipe Material	Quantity	Unit	Unit Price	Total
IPP L	NING REHABILITATION - PHASE 6					
	Mobilization		1	LS	12,900.00	12 900 00
1					102 20	2112 300 10
2	33" CIPP Lining (MH 1710-05 to MH 1710-01)	Unlined RCP	2,397	ᄕ	90	21.7 151.00
3	33" CIPP Lining (MH 1710-01 to MH 5117-05	F-Lock RCP	2,715	Ŀ	124 22	1002 00/ 20
4	36" CIPP Uning (MH 5117-05 to MH 1708-13)	T-Lock RCP	9,686	LF	124,20	1,203,008.20
			SU	BTOTAL - CIPE	P LINING REHABILITATION	1,720,421.60
MAN	HOLE REHABILITATION & COATING - PHASE 6					,
1	Rehabilitate Existing Sewer Manholes		653	VF		
2	Coat New CIP MH Base for 84" Manhole Removal/R (MH 1708-34A)	eplacement	1	EA		
3	Coat New CIP MH Base for 120" Manhole Removal/ (MH 1708-36, 1708-34, 1708-25)	Replacement	3	EA		
4	Specification Item E.3.1 - Efforts for cosmetic finish virregularity free uniform finish, free from trowel madepressions, ripples, waves, bubbles, bumps or crack coaling layer using an approved repair method. To profile for coating.	rks, volds, king in the final				,
			280	HR		
5	1-Inch additional underlayment application for extra deteriorated manholes	emely	164	VF		
			OTBUS	TAL - MH REH	ABILITATION & COATINGS	
		•	*Please List You	ır installation	Days Required to Complete	Your Own Scope of Work (Calendar Days
					MH Coatings	
		**Please tis	at any MH's That	Require CIPP	1	rei Removals or Base Modifications Belov
		TU BULLTO INT	PROCESTAN DE	LIADUITAT	ION BID RECAP	
	NOR				····	
		1	Phase 1 Rehabil	itation Sectio	n TOTAL BASÉ BID (ITEM A)	
			Phase 2 Rehabil	litation Sectio	on TOTAL BASE BID (ITEM B)	
			Phose 3 Rehabil	litation Sectio	on TOTAL BASE BID (ITEM C)	
			Phasé 4 Rehabi	litation Sectio	on TOTAL BASE BID (ITEM D)	
			Phase 5 Rehabi	litation Section	on TOTAL BASE BID (ITEM E)	
			Phase 6 Rehabi	litation Sectio	on TOTAL BASE BID (ITEM F)	
			MH Coatings - !	5 Year Warrat	nty/Maintenance Bond COS	
					PROJECT TOTAL	

.

	G	ADD ALTERNATES					
		ADD ALIERIVATE	· · · · · · · · · · · · · · · · · · ·				
	Item N	umber & Description		Quantity	Unit	Unit Price	Total
		Rehabilitate & Coat I	Existing Sabino Creek Siphon Inlet & Outlet			1	
	1		new redwood diversion stop logs. (*B&F to				
		provide new precast	structure lids and openings)	1	LS		
		CIPP lining repair for	removal of bumps, or wrinkles using an epox	Y		00100	00/ 5
	2	product in coated AC	CP Reaches	1	EA	881.30	881.30
	3	HCS Reinstatement		1	EA		
	-	Troo vieniateleniati		-		l	
9	items	s to Include with	Bid				
-	1.	CIPP Shot Schedule					
	2.	Crew Availability & C	rew Size				
	3	Key Personnal					
	4	Current Workload					
	5		uire modification for CIPP Lining Access				
	6		uirements for CIPP construction water and su	pply pipe (if required	j)		
					•		
10	Proje	ct Duration					
	-		r agrees to complete their own scope of work	in the allotted Cale	ndar Davs list	ed above on the bid schedul	e.
			due to non-performance will result in Liquida				_
			,				
11	Total	Installation Day	s - Phases 1 to 6				
		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	()				
	CIPP IN	STALLATION CALENDA	AR DAYS	,			
	MH CO	ATING INSTALLATION	CALENDARS DAYS				
12	Bond						
	Total		to be added to this Bid if Bidder is required t				
		╨┸┸	The subcontractor must list their bonding co	mpany and agent w	th a phone n	nuper and contact name.	
			Travelers Casualty and	S Curety Co	manır a	F Amorrian	
	Surety	Company:	Traverers casuarry and	1 Surecy Co	iipany o.	L America	
		(c)	JW Terrill				
	Agent/	rirm:	OW TELLILL			· · · · · · · · · · · · · · · · · · ·	
	A 1	Nama (Dhana Numbo	Dana Dragoy	314.594.265	55		
	Agent	Name/Phone Number	-				•
	2-46	R 2rd Tipe Subso	ntractors /Fishs to Fishsontrastor	c)			
13			ntractors (Subs to Subcontractor				_
		-	tractors are proposed to perform work on this	Project. Inis list is	complete and	no additional subcontractor	is
	snaji bi	e allowed on the brole	ct site without prior approval:				
			0 1			Scope of Work	
	Compa	any	<u>Phone</u>			Scope of work	
			· · · · · · · · · · · · · · · · · · ·				•
							•
		······································	<u> </u>				•
				···			•

		ors and Products will be used t shall include proposed liner de			and no changes shall be allowed nd resin supplier below).
	Approved Supplier/Vendor		Product/Mater	isis Sunnitad	
-		1/Mbbe		natival	
					
	CIPP Bidder has included prop CIPP Bidder has include pre-li	osed liner and resin specificati osed liner mill thickness with E ner material with Bid: as included Performance Histor	ld:	tal Specifications	Yes
15	Insurance	neets or exceeds the PCRWRD's	contract require	ments:	Yes X No
		heir insurance company and ag			7
	Insurance Company:	Liberty Mutua	l		
	Agent/Firm:	Lockton Compani	.es		
	Agent Name / Phone Numbe	Nancy N	Mueller	314.812.3294	
16		intractor's Pollution Liability co I liability insurance coverage m			,000,000 / event and \$4,000,000
17	Technical Specificati CCTV Pre-Video NRI AS-Builts ACP CIPP Uning Invi Manhole Investigati Manhole Investigati	CRWRD Project No. 3NRI14 da lons - PCRWRD Project No. 3NF estigation Videos (Pre & Post Li ion Report performed by Brow ion Photos of MH Interior Plan provided by B&F Contract	R114 dated 2/05/2 Ining) In and Caldwell		
18	B Liquidated Damages Additional Installation days to of the Flow Management Sy CIPP Lining = \$11,192,00 ner MH Coatings = \$2,680,00 ne	for CIPP or MH Coating Work, o stem. Liquidated Damages are <u>r calendar dav</u>	outside of your Ca calculated as foll	iendar Days listed above w ows:	il result in liquidated damages to cover the costs
1	9 Acknowledgments				
	Addendum #1 Addendum #2 Addendum #3	Dated 10/2/2014 Dated 10/7/2014 Dated 10/9/2014	Addendum Addendum Addendum		Dated Dated

14 Approved Suppliers/Vendors

Bidder Acknowledgement:

Bidder acknowledges the above addenda and once submitted, this Bid may not be altered, amended or withdrawn for a period of (90) days without prior written consent of B&F Contracting, Inc.

20 Signature

Didder herein agrees that if awarded the work on the basis of this Bid Proposal, he will enter into and execute a sub-contract agreement with B&F Contracting Inc.

Company / Bidder:	Insituform Technologies, LLC
Signature:	Leves Carroll
Title:	Denise Carroll, Contracting and Attesting Officer
Date:	October 13, 2014
Arizona Contractors Licer	sse No: 277787




`		Technolo,	gies	, LLC.													
			٦,	Import	P6	Т			base								
hase	uration (in Days)	of (Reach) ID	ment	petreum MH	rustreum MH	nversion Direction	version MH	IMH	H requiring CIPP wersion acces, nocharrel removal or b coliferien	pstream Depth (VF)	wnstream Depth (VF)	all (LP)		~	install Thickness NOT DESIGN (mm)	Plan Length (LF)	Shot Length (LF)
- #	e e	- 25	ĕ	8716-20	8716-19	<u> </u>	- <u>-</u> =	<u> </u>	M M M M M M M M M M M M M M M M M M M	12.38	යි 10.5	-5.9	Street E Woodland Rd	(C)	7.50	507	- 6
		1	3	8716-19 8715-18	8716-18 8716-17	Downstream	8716-20	8716-17	Need minor tree trimming on MH8716-20	12.3	12.3 12.88	1,6 2,2	E Woodland Rd	15 15	7,50 7,50	519.57 518.67 532.28	1545.24
		2	5	8716-17 8716-16 8716-15	8716-16 8716-15 8716-14	Downstream	8716-17	8716-14	Dione	12.71	12.71 12.31	24	7 E Woodfand Rd	15	7.50	485 505.95	1523.23
			7 8	8716-14 8716-13	8716-13 8729-01	-	0710-11	0,10-14		12 11,45	11.45 11.45	2.6		15 15	7,50 7.50	505,27 155,13	
1 1	7	3	10	8729-01 8716-12 8716-11	8716-12 8716-11	Downstresm	8716-14	8716-10	None	11.39	11,39	3.4	E Woodland Rd	15 15	7.60 7.60	348.25 489,5 494.28	1992.43
		4	12	8716-10 8716-09	8716-10 8716-09 8716-08	COMEZIGNI	0710-14	3710-10	THOSE .	11.25	11,25 10,8 10,9	2.1 2.0 1,7	E Woodland Rd	18	7.50	577.38 580.18	100245
			14	8716-08 8716-07	8716-07 8716-06	Downstreem	8716-10	8716-07	None	10.9 10.89	10.89 11.25	2.1 0.8	Z Tanqua Verde	18	7.50 7.50	616.43 195.25	1773.99
		6	1 17	8716-06 8716-05 8716-03	8716-06 8716-04 8716-02	Upstream	8716-04 8716-02	8716-07 8716-03	None None	11,25 14		-1, 4,1 2,4	Tanque Verde Tanque Verde (drt version) exament	18 18	7,50 7,50 7,50	284,3 464,66 264,77	944.1 264.77
\vdash		7 8	19 20	8716-02 4466-OUT	4456-IN 1811-01A	Downstream Upstream	8716-02 1811-01A	4456-IN 4466-OUT	None None	10,72 10.81	9,8 11.3	-0.0		24 24	9.00	410 150	410 150
		9	71 72 23	1811-01A 1700-16	1700-16 1700-15	Upstream	1700-16	1811-01A	None	15.68	15.88 13.65	41 42	9 eastment 4 North Partano Rd	27	9,00 12,00	278 433.17	278
		10	24	1700-15 6295-04 6295-03	6295-04 6295-03 6295-02	1				14.04	14.04 11.87 12.32	-0.2 2,6	d comment comment	27		38.12 294.27 375.16	
			26	6295-02 6295-01	6295-01 1700-13	Downstream	1700-16	1700-13	None	12.32	13.01	1.0	ecoment	27 27	10.50 10,50	141.4 249.99	1532.11
2	9	11	1 29	1700-13 1700-12 1700-11	1700-12	Downstream	1700-13	1700-11	MH 1700-13 unexposed during site Visit. Typical driving access needed for Inversion MH 1700-13	11.8 11.8	11.8 11.3 12.9	2.5	6 eesement	27 27	10.50 10.50	686.8 716 288.57	1401.8
		13		1700-10	1700-10 1700-09 1700-08	Upstream	1700-08	1700-10	None	12.9 10.99	10.99	-0.9 2.9 0.7	driveway of 133 N Lodge Rd Upstream MH is behind well of driveway essement	27 27	10,50	288.57 439.5 145.54	288.57 585.04
		14	33 34	1700-08 1700-07A	1700-07A 1700-07					10.71 9.04	9.04 6.83	3.1	Caille Los Arboles next to driveway 7302 Calle Los Arboles	27	10.50 10.50	783.11 266.6	
		15	36	1700-06A	1700-06A 1700-06 1700-06	Downstream	1700-08	1700-06A	None	12.56	12.56 13.72	-29	7 ensement	27	10.50	202.48 359.63	1252.19
ļ		16	38 39	1700-05	1700-04 8240-01	Downstream Downstream	1700-06A	1700-04 8240-01	None MH 1700-04 buried during site visit	14.86	14.86 0 16.01	1,3 2480,6 -2475.5	1 Sabino Carryon Rd Calle Tabara	27	10.50 10.50	311 376 781	1046.69 781
		17	40	8240-01 1700-02	1700-02 1700-01					16.01 17,42	17,42 17,8	-0.5 2476.1	Calle Tabara S one S of Riverbend PL	27	12.00	173 412	
		18	43	1700-01 1714-12 8705-01A	1714-12 8705-01A 1714-11	Upstream	1714-12	8240-01	None	22,48	22,48 21,48 20,98	-2473.9 2 1.5	7 ease S of Riverband Cir 4 easement 6 easement	. 30	13.50 15.00 13.50	467 470.75 139.43	1052
			45	1714-11 4623-06	4623-06 1714-10	Upstream	4823-06	1714-12	None	20,98		4.9	9 9000 S of Cloud Rd	30	13.50	320 640	930.18
		19	48	1714-10 4823-12	4623-12 1714-09	Downstream	4623-06	1714-09	None	16.68 13.94	13.94	3,0	B Crimson Sage 1 Wood Lilly Ct	30	12.00	241,48 567,85 750,62	1439,33
3,	12	20	50	1714-09 1714-08 8282-01	1714-08 8282-01 1714-07	Downstream	1714-09	1714-07	Across resolute to provident through dist hormate inventors ANA 1714-79	12.55	12.55 13.78 15.99	0.9 0.2	7 gese S of Cloud Rd	. 30	12.00	750,62 56,2 822,43	1629,25
		21	53	1714-07 1714-06	1714-06 1714-05A	Downstream	1714-07	1714-06A	Access needs to be provided through dirt berm to inversion MH 1714-09 Access road improved on MH 1714-07 and brush removed for inversion equipment around MH	15.99	11.85 9.26	7,1	6 ense S of Country Club Vista Pl. ense S of Country Club Vista Dr	88	12,00	983 840	1823
		22	56	1714-05	1714-05 1714-04 1714-03	Downstream	1714 OKA	1714-03	Named to 164 4764 664 for advanta assessed a small for the behavior	11.38	11.38 8.88 13.4	-1.0 6.3 -2.7	5 ecco S of Calle Agua Verde 5 Son Sebastion Dr ecco	30	10.50	160.51 737.76	1655.94
			57 58	1714-03 1714-02	1714-02 1714-01A	- ILOWISINGS	1714-004	1714-05	Inversion MH 1714-05A in private property, possible tree trimming.	13,4	14,92	-1.0 1.	Calle Rosarto	30	12.00	757.67 206.08 604	1000.54
		23	59	1714-01A	1714-01 8964-01		4744 00	F000 00		39.8	14.96 39,8 34,72	-21. 4.6	Graycroft Rd Graycroft Rd	30	18,00	206 50.42	
		24	62	5033-03 1801-01	5033-03 1801-01 1712-09	Downstream Downstream	5033-03	1712-09	None None	34.72 23.72 24.45	23,72 24.45 15.23	10.9	ease W of Craycroft	30	18,00 15,00 15,00	203 714.7	917.7
		25	64	1712-09	1712-08 1712-07	Downstream	1712-09	1712-07	Might be able to do Upstream if problem with the owner access at Inversion manhole 1712-09	15.23 10.03	10.03 10.46 15.99	7.7 2.0 0.8	MH in driveway ease S of River House Rd	39	12.00 10.60	246 835	1081
4	В	26	67	1712-07 1712-06 1712-05	1712-06 1712-05 1712-04	Downstream.	1712-07	1712-05	Need access to private property fence and driveway at MH 1712-07 Tree trimming, possible driveway improvement for vehicle access and maybe	I 15.99	9.79	9.1	6 eese S of River House Rd	33	12.00 13.50 12.00	682 665	1347
		27	69 70	1712-04 1712-03	1712-03 1712-02	Downstream	1712-05	1712-03	some clearing at MH 1712-05 Tree trimming, possible drivoway improvement for vehicle access and maybe some	12.62	11.7 12.62 12.85	-0,2 0,4 2,0	ease S of Sinuoso 1 ease S of Sinuoso	33 33	12,00	463 590	1044
\vdash		29	71	1712-02	1712-01 1710-13	Downstream	1712-03	1712-01	dearing at MH 1712-03 Need access through the park, ballards of steel posts removed, trail improment for	12.85 14.45	14.45	1.4 -0.7	7 ease E of Swan 8 sase W of Swan	33	12.00	466 535	1056
		30	74	1710-13 1710-12 1710-11	1710-12 1710-11 8980-01	Upstream	1710-12	1712-01	vehicle access and cirt work around the MH 1710-12 Need access through the park, ballards of steel pods removed, trail improment for	18.61	18,61 20,3 19,85	-0.3 -0.3 0.8	ocean Sof Coachilight	33	15,00 15,00 15.00	711.88 457 251	1246,88
5	9	31	76 77	8980-01 1710-10	1710-10 1710-09	Downstream Upstream	1710-12 1710-09	1710-10 1710-10	vehicle access and dirt work around the MH 1710-12 Need access to MH 1710-09 - Fence removal/ destring	19.85	16.88 24.36	2,0 -3,3	6000 S of River Celk Lane ease S of River Oak PL	33	15.00 16.50	450 715	1158_ 716
		32	78 79	1710-09 1710-08	1710-08 1710-07	Downstream	1710-09	1710-07	Need access to MH 1710-09 - Fence removal / clearing	24,36 25.3	25.3 23.36	-0.2 3.0	7 eeen Sof River Rd 6 eess Sof River Rd	33	16.50 16.50	543.09 369	902.09
ļ		33 34 35	81	1710-06	1710-06 1710-05	Downstream Downstream	1710-06 1710-06	1710-07 1710-05	None None	25.3 25.58	25.58 25.58 23.45	0.6 1.2 3.	4 River Rd	33	16.50 16.50	550	919 550
		36	83	1710-04 1710-03	1710-03 1710-02	Upstream	1710-03	1710-05	None	23,45 20,28	23,45 20,28 12,39	7,1 11.1	3 Rüyer Rd	33	16.50 15.00	682 740	1176
		36		1710-01	1710-01 1708-36 1708-35	Downstream	1710-03	1708-36	None	12.39	10.64 10.64 14.28	4.1 0.7 -1.4				472.34 119.34 636	1331.68
		27	88 89	1708-35 1708-34A	1708-34A 1708-34	Downstream	1708-36	1708-34	None	14.28 14.96	14.96	1,6 0,3	7 N. Sutton Lane 2 N. Sutton Lane	33	13,50 13,50	629 66	1321
		38	90	1708-34 1708-33	1708-33 5117-06	Downstream	1708-34	5117-06	None	14,98 13.36	13.36	3.6	1 E. Roger Rd 3 E. Roger Rd	88	13.50 12.00	615 625	1240
		39 40	83	5117-06 5117-05 1708-30	5117-05 1708-30 1708-29	Downstream	6117-06	6117-05	None	11.32	11,32 15,38 17.8	-0.0 -2.7 -2.0	7 E. River Rd.	33 36	13.50 15.00	40,29 432,22 118,36	40.29_
		41	96 96	1708-29 1708-28A	1708-28A 1708-28	Downstream	5117-05	1708-28A	None	17.8 16.27	15.27 17.66	3.6 -0.1	8 E. River Rd. 9 E. River Rd.	36	15.00	118.36 511.26 764.58	1061,83
		41 42 43	97 98	1708-28 1708-27	1708-27 1708-26	Downstream Downstream		1708-27 1708-26	None None	22.88	31.35	-4.4 -5.8	7 E. River Rd.	36	16,50	389.09 587	1123,67 587
6	25	43	100	1708-26 1708-25 1708-24	1708-25 1708-24 5293-02	Downstream	1708-26	1708-25 5293-02	None None	28.5	33,76 28.5 27.4	-0.7 6.3 2.	4 eessment	36 36	21.00 21.00 19.50	676.37 302.28	676,37 451.28
		45	102 103	5293-02 5293-01	5293-01 1708-23	4			Private property access needed to M.H., possibly some minor dirt work if needed at	27.A 25.8	25.8 23.7	3,0	3 experient 4 experient	36 36	18.00 18.00	123.96 132.08 519	
			105	1708-23 1708-22 1708-21	1708-22 1708-21 1708-20	Upstream	1708-22	5293-02	MH 1708-22	18.89	18.89 18.44 17.7	3.5	9 easement 2 Easement 2 Easement	36	15.00	519 392 320	774.94
		46	107 108	1708-20 3963-01	3963-01 1716-01	=				17.7 15.27	15.27 14.78	2356,2 -2354,2	4 Ensement	36 36	15,00 13,50		
			109	1716-01 1708-19A	1708-19A 1708-19	Downstream	1708-22	1708-19A	None	14.78 16.73	16.73	0.7 2.6	9 0	36	15.00	43 534	1185
		47	112	1708-19 1708-18A 1708-18	1708-18A 1708-18 8804-01	Downstream	1708-19A	8804-01	MH 1709-19 is buried, need located and opened for access to out liner. As an alternative, we can line through it if the CIPP does not have to be cut in the MH. MH 8804-01 needsminor dearing.	18.35	18,35 16 16.34	-0.5 2351.4 -2348.3	1 N. Cancion	36 38	15,00	392.8 187 39	1162.8
		48	114	8804-01 1708-17	1708-17 1708-16	Upstream	1708-16	8804-01	MH 8804-01 needs minor clearing	16.34	15,71 22.16	29 -4	5 Essenant 2 Essenant	. 36	15,00 15,00 16,50	638_ 488	1126
		49	116	1708-16 1708-15	1708-15 1708-14	Downstream	1708-16	1708-13A		22,16 20,3	20.53	2.5 0	3 Eastment 6 Eastment	36 36	16.50 16.50	289 104	
		50	119	1708-14 1708-13A 8809-01	1708-13A 8809-01 1708-13	Downstream	1708-13A	1708-13A	None None	20.17 17.13	20.17 17.13 15.78	1.6 5.0 2.2	7] Ezement	36 36	16.50 16.50	391 617 158.47	775,47
						,			• • • • • • • • • • • • • • • • • • • •								



NRI Rehabilitation Pima County Project No. 3NRI14 - B & F Contracting, Inc Insituform's List of Current Workload in AZ, NV and CA with the assigned key personnel (Ref - Bid Form 1.38)

	4	,			General	
Project in Backlog	Contract Value	Timeline	Project Manager	Field Engineer	Superintendent	Superintendent
City of Phoenix Small Diameter Rehab (AZ)	\$1.55 million	Sep 2014 to Jan 2015	Seth Ganesan	Mark Werts	Terry White	Peter Hryciw until NRI Start/ Tempe Crew 2 from NRI start
SEI Rehab Phase II Simpson Street	\$0.4 million	Nov/ Dec 2014	Seth Ganesan	Mark Werts	Terry White	Peter Hryciw and/ or Tempe Crew 2 depending on NRI Schedule
PIMA County JOC Work Orders (AZ)	As released	Oct 2014 to Oct 2015	Seth Ganesan	Mark Werts	Terry White	Peter Hryciw between NRI phases/ Tempe Crew 2 during NRI
Scottsdale JOC Work Orders (AZ) Nevada Irrigation District M2013-03 (NV)	As released \$0.13 million	Jan 2015 to Dec 2015 Nov-14	Seth Ganesan	Mark Werts Cory Wagner	Terry White	Peter Hryciw between NRI phases/ Tempe Crew 2 during NRI Todd McMillan
LA County Sanitation District # 5 (CA)	\$10.6 million	Sep 2014 to Jan 2015	Roberto Rizo	Ben Smith	Michael Gallegos	Raul Ruiz
Orange County Sanitation District/ Kiewit Newport Beach Force Main Ph 1 (CA)	\$2.56 million	Jan 2015 to Mar 2015	Roberto Rizo	Yan Therube	Mark Hairston	Fernando Avila
Orange County Sanitation District/ Kiewit Newport Beach Force Main Ph 2 (CA)	\$2 million	Oct 2015 to Jan 2016	Roberto Rizo	Yan Therube	Mark Hairston	Fernando Avila
Imperial Irrigation Merced, CA #1140009 HWY 59	\$0.07 million \$0.53 million	Q4 2014 Oct-14	Roberto Rizo Richard Gann	Yan Therube Cory Wagner	Michael Gallegos JD Horton	Fernando Avila Todd McMillan
Beale Air Force Base Ross Valley Sanitary District Magnolia Avenue Truck Rehab	\$0.52 million \$0.17 million	Q3 and Q4 2015 Nov-14	Richard Gann Richard Gann	Cory Wagner Cory Wagner	JD Horton JD Horton	Todd McMillan Todd McMillan
Sacramento Area Sewer District CA Franklin Blvd	\$0.19 million	Nov-14	Richard Gann	Cory Wagner	JD Horton	Todd McMillan
Napa Sanitation District North Napa Cipp Lining	\$0.53 million	Dec-14	Richard Gann	Cory Wagner	JD Horton	Todd McMillan
Palo Alto, CA Sanitary Sewer Rehab Project	\$0.17 million	Dec-14	Richard Gann	Cory Wagner	JD Horton	Todd McMillan





NRI Rehabilitation Pima County Project No. 3NRI14 - B & F Contracting, Inc List of Trenching requirements for CIPP construction water and supply pipe

Manhole	Purpose of trench	Location
1710-06	For inversion water	Cut from south side of River Rd to center
1710-03	For inversion water	Cut from south side of River Rd to center
1708-36	For inversion water	Cut from south side of River Rd to center
1708-28A	For inversion water	North cut from River Rd to center median
1708-26	For inversion water	South side cut River Rd to center mendian

CONTRACTOR EXPERIENCE FORM

Provide list of experience per the requirements of Section 713, Paragraph 713.5 of the Special Provisions.

<u>Failure to provide complete information on this form may deem your bid non-responsive.</u>

1.	PROJECT: _Palm Desert Trunk Sewer Rehab DATE COMPLETED: _Sept. 2014
	NAME OF OWNER:Coachella Valley Water District
	CONTACT PERSON: _Luis TamaizPHONE NUMBER: 562-755-0535_
	SIZE OF CIPP INSTALLED: 33&36" TOTAL LENGTH INSTALLED: 16,882FEET
	LONGEST INDIVIDUAL LENGTH OF CIPP INSTALLED: 1300 FEE
2.	PROJECT:Coachella Ave 62 DATE COMPLETED: _May 2014
	NAME OF OWNER: Coachella Valley Water District
	CONTACT PERSON: Luis Tamaiz PHONE NUMBER: 562-755-0535
	SIZE OF CIPP INSTALLED: 20,33,42 TOTAL LENGTH INSTALLED: 27,000 FEE
	LONGEST INDIVIDUAL LENGTH OF CIPP INSTALLED:800FEET
3.	PROJECT: Central Trunk Sanitary Rehab DATE COMPLETED: Sept 2010
	NAME OF OWNER: Sacramento Area Sewer District
	CONTACT PERSON: Amber ParmerPHONE NUMBER: 916-876-5996
	SIZE OF CIPP INSTALLED: 42,48,54,60" TOTAL LENGTH INSTALLED: 41,665 FEE
	LONGEST INDIVIDUAL LENGTH OF CIPP INSTALLED: _2600FEE
4.	PROJECT: Gravity Main DIP Rehab DATE COMPLETED: Feb 2013
	NAME OF OWNER: City of Vista CA
	CONTACT PERSON: Tony White PHONE NUMBER: 619-212-3554
	SIZE OF CIPP INSTALLED: 36 TOTAL LENGTH INSTALLED: 10,000 FEET
	LONGEST INDIVIDUAL LENGTH OF CIPP INSTALLED: 800FEET
5.	PROJECT: SARI Repairs to RCP reaches IVA to IVB DATE COMPLETED: Nov 2011
	NAME OF OWNER: Santa Ana Watershed Project Authority
	CONTACT PERSON: David Rhuel PHONE NUMBER: 951-354-4223
	SIZE OF CIPP INSTALLED: 24 TOTAL LENGTH INSTALLED: 24,669 FEET
	LONGEST INDIVIDUAL OF CIPP LENGTH INSTALLED: 2200 FEET

SUPERINTENDENT QUALIFICATION FORM

Provide the name of the construction superintendent/superintendents to be assigned to the above stated project. Each qualified superintendent shall have a minimum of three (3) years CIPP lining supervisory field experience on a least 3 successfully completed projects containing at least a total of 3,000 LF of 6"-10" or larger CIPP liner including three (3) years flow diversion supervisory field experience per the requirements of Section 713, Paragraph 713.5 of Special Provisions.

Failure to provide complete information on this form may deem your bid non-responsive.

SUPERINTENDENT NAME: Peter Hryciw
1. PROJECT: Palm Desert DATE COMPLETED
NAME & ADDRESS OF OWNER:See Contractor Form
Coachella Valley Water - 75525 Hovley Ln E, Palm Desert, CA 92211
CONTACT PERSON: PHONE NUMBER
SIZE OF CIPP INSTALLED: _33 TOTAL TIME ACTING AS SUPERINTENDENT: _1.5 MONTHS
INCLUDED FLOW DIVERSION? CHECK ONE YES NO
INCLUDED FLOW DIVERSION? CHECK ONE YES NO
2. PROJECT:Coachella 62 DATE COMPLETED
NAME & ADDRESS OF OWNER:See Contractor Form
Coachella Valley Water - 75525 Hovley Ln E, Palm Desert, CA 92211
CONTACT PERSON: PHONE NUMBER
SIZE OF CIPP INSTALLED: _42 TOTAL TIME ACTING AS SUPERINTENDENT: _1 MONTHS
INCLUDED FLOW DIVERSION? CHECK ONE YES NO
3. PROJECT: _Pima County JOC—B&F and KE&G70,881' DATE COMPLETED 2012-Current
NAME & ADDRESS OF OWNER: Pima County Wastewater
CONTACT PERSON: Dan Foley/Brian Janski PHONE NUMBER 520-840-9785/520-940-8423
SIZE OF CIPP INSTALLED: 6,8,10,12,15,24,&60" TOTAL TIME ACTING AS SUPERINTENDENT: 24_MONTHS
INCLUDED FLOW DIVERSION? CHECK ONE □ YES □ NO
4. PROJECT: Phoenix JOC DATE COMPLETED Dec 2013
NAME & ADDRESS OF OWNER: City of Phoenix, 200 W. Washington Street Floor 9, Phoenix AZ 85003
CONTACT PERSON: Steve Fernandez PHONE NUMBER 602-495-0724
SIZE OF CIPP INSTALLED: 8-15" TOTAL TIME ACTING AS SUPERINTENDENT: _36MONTHS
INCLUDED FLOW DIVERSION? CHECK ONE YES NO

SUPERINTENDENT QUALIFICATION FORM CONTINUED

5. PROJECT:	DATE COMPLETED	
	PHONE NUMBER	
	TOTAL TIME ACTING AS SUPERINTENDENT:	MONTHS
INCLUDED FLOW DIVERSION? C	HECK ONE DIYES DINO	
6. PROJECT:	DATE COMPLETED	
NAME & ADDRESS OF OWNER: _		
CONTACT PERSON:	PHONE NUMBER	
	TOTAL TIME ACTING AS SUPERINTENDENT:	
INCLUDED FLOW DIVERSION? C		
11020222 120 11 21 22 23 25 11 0		
7. PROJECT:	DATE COMPLETED	
CONTACT PERSON:	PHONE NUMBER	
SIZE OF CIPP INSTALLED:	TOTAL TIME ACTING AS SUPERINTENDENT:	MONTHS
INCLUDED FLOW DIVERSION? C	HECK ONE D YES DNO	
0 DDOUGCT.	DATE COMBLETED	
NAME & ADDRESS OF OWNER.	DATE COMPLETED	
NAME & ADDRESS OF OWNER: _		
CONTACT PERSON:	PHONE NUMBER	
SIZE OF CIPP INSTALLED:	TOTAL TIME ACTING AS SUPERINTENDENT:	MONTHS
INCLUDED FLOW DIVERSION? C	HECK ONE D YES D NO	
9 PROJECT:	DATE COMPLETED	
CONTACT PERSON:	PHONE NUMBER	
	TOTAL TIME ACTING AS SUPERINTENDENT:	
INCLUDED FLOW DIVERSION? C		
USE SEPARATE SHEET FOR EAC	H DESIGNATED SUPERINTENDANT	
X:\Eng\ Shared Data\ESU\Section (Common Shared Folder\Spdway-Main CIPP\Bid Schedule and	CONTRACTOR
FORMS_9-02-11.doc		



<u>CIPP Felt Liner Material</u> <u>Manufactured by Insituform Technologies, Inc.</u>

"The ITI CIPP tubes comply with the industry standards as stipulated within ASTM F1216 and ASTM D5813. The needled polyester felt sewn seam tube construction exceeds all strengths required within standard D5813: Sections 5. Materials and Manufacture and 6.1 Requirements, Fabric Tube Strength."

-Felt Density ~ 1.38 g/cc; flexible membrane density ~ 0.93 g/cc; void volume $\sim 85\%$



CERTIFICATE OF COMPLIANCE

Date: October 10, 2014

Project: NRI Rehabilitation Pima County Project No. 3NRI14

102T/TA is a resin that is manufactured in the United States of America and has been approved by Insituform Technologies, LLC. for use in Insituform projects. 102T/TA resin has a successful history in both lab conditions and actual field installations and meets the chemical resistance recommendations of ASTM F1216 and ASTM D5813. We recommend the following physical properties for Insituform design when using the 102T/TA polyester resin system:

The above values were derived from samples tested in accordance with modified ASTM D-790 when used and installed in accordance with procedures recommended by Insituform Technologies, LLC.

INSITUFORM TECHNOLOGIES, LLC.

Eugene Zaltsman

Sr. Applications Engineer

STATE OF MISSOURI COUNTY OF ST. LOUIS

Subscribed and sworn to before me on Friday, October 10, 2014.

Notary Public

DIANE PARTRIDGE
Notary Public - Notary Seal
STATE OF MISSOURI
St. Louis County

My Commission Expires: July 8, 2016 Commission # 12595471



17988 Edison Chesterfield, MO 63005 Tel: 636-530-8000 Fax: 636-530-8744 www.insituform.com

CERTIFICATE OF COMPLIANCE

Date: October 10, 2014

Project: NRI Rehabilitation Pima County Project No. 3NRI14

To Whom It May Concern:

This letter certifies that Insituform tubes are manufactured in Batesville, Mississippi, USA, by Insituform Technologies, LLC and meet all relevant specifications for a cured-in-place pipe product: ASTM D 5813, ASTM F 1216, and ASTM F 1743. Insituform tubes have been manufactured in the USA since 1981.

The finished tube is manufactured using multiple layers of polyester felt, with one layer coated with Polypropylene plastic. The layers are cut/slit to the desired width, and sewn concentrically to form the final tube. The coated layer is also sealed at the seam, using an extrusion or taping process. The extrusion process is used on the standard (inverted) tubes. The standard (inverted) tubes are manufactured with the coated layer on the outside.

Felt production is achieved by a non-woven needle punch process using Polyester fiber. The finished product is tested for thickness under a specified load and for tensile strength in accordance with ASTM D 5813. The fabric tube has a minimum tensile strength of 750 psi (5 MPa) in both the longitudinal and the transverse direction. The seam strength of the tube is also tested on a regular basis and also meets or exceeds the minimum tensile strength of 750 psi (5 MPa) in both longitudinal and transverse direction. For Quality Assurance purposes, the material is also tested for weight and thickness.

All standard (inverted) tubes are run through a dye bath prior to shipment to ensure there are no leaks. Following the inspection process all tubes are printed with yard marks.

All tubes with tapers, transitions, or any change in tube diameter or thickness are produced under the same specifications, with the same materials, and meet the same material testing requirements as the standard tube.

The quality system used by Insituform Technologies, LLC is ISO 9001:2008 certified.

The end use of the Insituform tube is to rehabilitate sewer and drainage pipes to increase the life of the pipe and prevent a dig and replacement of a pipe.

Please contact us directly with any questions you may have.

Sincerely,

INSITUFORM TECHNOLOGIES, LLC

Eugene Zaltsman

Sr. Applications Engineer

STATE OF MISSOURI

COUNTY OF ST. LOUIS

Subscribed and sworn to before me on Friday, October 10, 2014.

Mane Latrider

DIANE PARTRIDGE
Notary Public - Notary Seal
STATE OF MISSOURI
St. Louis County
My Commission Expires: July 8, 2016
Commission # 12595471



Worldwide Pipeline

17999 Edison Ave.

Tel: (636) 530-8000

Rehabilitation

Chesterfield, MO 63005

Fax: (636) 530-8744

102T Series
Polyester Resin
October 2014

Polyester Resin for Gravity CIPP Applications

Insituform's 102T Series is a family of polyester resins for gravity sanitary and storm sewer applications. Resins currently approved for the 102T Series include:

AOC L758 Interplastic COR78-AT-559/5XX AOC L721 Insituform 102T

Typical Resin/Felt Properties

Flexural Strength, psi/MPa

4,500/31.5

ASTM D 790

Flexural Modulus, psi/MPa

500,000/2,760

ASTM D 790

Description

Insituform's 102T Series resins are comprised of filled, thixotropic polyester resins and are excellent applications for sanitary and storm sewers. These resins can also be used in some industrial applications. Polyester resins provide the corrosion resistance required for sanitary sewer applications and also provide the durability needed for long-term applications.

Features

Good physical properties, corrosion resistant, durable, good long-term properties, excellent catalyzed pot life, high heat distortion temperature and high molecular weight.

Safety

Safety guidelines are available in the appropriate Material Safety Data Sheet.

Detailed Information

Detailed information for any of the approved resins in the 102T Series can be provided upon request.



Worldwide Pipeline

17999 Edison Ave.

Tel: (636) 530-8000

Rehabilitation

Chesterfield, MO 63005

Fax: (636) 530-8744

102T Series
Polyester Resin
October 2014

Corrosion Testing for Gravity CIPP Applications

Insituform's 102T Series is a family of polyester resins for gravity sanitary and storm sewer applications. Resins currently approved for the 102T Series include:

AOC L758 Interplastic COR78-AT-559/5XX AOC L721 Insituform 102T

Typical Resin/Felt Properties

Flexural Strength, psi/MPa 4,500/31.5 ASTM D 790 Flexural Modulus, psi/MPa 500,000/2,760 ASTM D 790

Chemical Resistance Testing

CIPP laminates made from each of insituform's 102T Series resins are tested for chemical resistance in accordance with ASTM F1216 for one month exposure and ASTM D5813 for one year exposure.

Test Results

The results of the ASTM F 1216 and D 5813 chemical corrosion testing are shown in the attached data sheets ASTM F 1216 CORROSION TESTING RESULTS and ASTM D 5813 CORROSION TESTING RESULTS, respectively.

Detailed Information

Detailed information for any of the approved resins in the 102T Series can be provided upon request.

INSITUFORM TECHNOLOGIES 102T SERIES POLYESTER RESIN ASTM D 5813 CORROSION TESTING RESULTS

	AOC L7	721-LTA	AOCI	.758-LTI	COR 78-	AT-559/5XX	INSTUF	ORM 102T
	RETENTION	REQUIREMENT		REQUIREMENT	RETENTION	REQUIREMENT	RETENTION	REQUIREMENT
	AYTOE	BOX	VALUE	80%	VALUE	80%	VALUE	20%
CONTROL SAMPLE				1	l		L	
Flexural Modulus, psi	619,000		668,000		665,000		742,000	
1% NITRIC ACID								
Flexural Modulus, psi	533,000		561,000		620,000		700,000	1
% Retention	86%	PASSED	84%	PASSED	93%	PASSED	94%	PASSED
5% SULFURIC ACID			1					
Flexural Modulus, psi	562,000		572,000		637,000		728,000	
% Retention	91%	PASSED	86%	PASSED	96%	PASSED	98%	PASSED
100% ASTM FUEL C								1
FLEXURAL MODULUS, psi	587,000		666,000		595,000		744,000	
% Retention	95%	PASSED	100%	PASSED	89%	PASSED	100%	PASSED
100% VEGETABLE OIL							-	
FLEXURAL MODULUS, psi	634,000		665,000		674,000		753,000	
% Retention	102%	PASSED	100%	PASSED	101%	PASSED	101%	PASSED
0.10% DETERGENT								
Flexural Modulus, psi	550,000		591,000		638,000		633,000	
% Retention	89%	PASSED	89%	PASSED	96%	PASSED	85%	PASSED
0.10% SOAP								
Flexural Modulus, psi	553,000		651,000		645,000		654,000	
% Retention	89%	PASSED	98%	PASSED	97%	PASSED	88%	PASSED

June 2014

INSITUFORM TECHNOLOGIES 102T SERIES PLOYESTER RESIN ASTM F 1216 CORROSION TESTING RESULTS

		721-LTA		.758-LT1		T-559/5XX		DRM 102T
		REQUIREMENT		REQUIREMENT		REQUIREMENT	RETENTION	REQUIREMEN
	VALUE	80%	VALUE	80%	VALUE	80%	VALUE	80%
CONTROL SAMPLE								
FLEXURAL STRENGTH, psl	6,650		6,048	<u> </u>	8180		6,896	<u> </u>
FLEXURAL MODULUS, psi	590,000		722,710		665887	<u> </u>	750,666	ļ
TAP WATER								
FLEXURAL STRENGTH, psi	7,602		6,353		7896		6,703	
% RETENTION	114%	PASSED	100%	PASSED	97%	PASSED	97%	PASSED
FLEXURAL MODULUS, psi	551,706		632,142		648714		730,936	
% RETENTION	94%	PASSED	88%	PASSED	97%	PASSED	97%	PASSED
5% NITRIC ACID								
FLEXURAL STRENGTH, psi	7,464		5,924		7858		6,281	
% RETENTION	112%	PASSED	98%	PASSED	96%	PASSED	91%	PASSED
FLEXURAL MODULUS, psi	568,565		616,116		64D045		755,552	
% RETENTION	96%	PASSED	85%	PASSED	96%	PASSED	101%	PASSED
10% PHOSPHORIC ACID								
FLEXURAL STRENGTH, psi	7,623		6,291		7709		7,177	
% RETENTION	115%	PASSED	100%	PASSED	94%	PASSED	104%	PASSED
FLEXURAL MODULUS, psi	544,623		678,126		663334		757,194	
% RETENTION	92%	PASSED	94%	PASSED	100%	PASSED	101%	PASSED
10% SULFURIC ACID								
FLEXURAL STRENGTH, psi	7,557		6,236		7774		6,989	
% RETENTION	114%	PASSED	100%	PASSED	95%	PASSED	101%	PASSED
FLEXURAL MODULUS, psi	575,028		646,307		667650		745,008	
% RETENTION	97%	PASSED	90%	PASSED	100%	PASSED	99%	PASSED
100% GASOLINE				<u> </u>				
FLEXURAL STRENGTH, psl	8,397		6,576		8527		7,639	
% RETENTION	126%	PASSED	100%	PASSED	104%	PASSED	111%	PASSED
FLEXURAL MODULUS, psi	599,527		695,498		656421		765,138	
% RETENTION	102%	PASSED	96%	PASSED	99%	PASSED	102%	PASSED
100% VEGETABLE OIL				<u> </u>				
FLEXURAL STRENGTH, psl	7,852		6,460		8039		6,772	
% RETENTION	118%	PASSED	100%	PASSED	98%	PASSED	98%	PASSED
FLEXURAL MODULUS, psi	624,613	PROJED	685,065	PASSED	675249	FAGSED	759,969	FASSED
% RETENTION	106%	PASSED	95%	PASSED	101%	PASSED	101%	PASSED
0.1% DETERGENT								
FLEXURAL STRENGTH, ps	7,125		6,396	<u> </u>	7697		6,712	
% RETENTION	107%	PASSED	100%	PASSED	94%	PASSED	97%	PASSED
FLEXURAL MODULUS, ps	548,941	I FWJLD	682,070	- FAGLU	638719	IAJED	737,963	- FAGUE
% RETENTION	93%	PASSED	94%	PASSED	96%	PASSED	98%	PASSED
0.1% SOAP								
FLEXURAL STRENGTH, psi	6.771		5,906		7778		7,164	
% RETENTION	6,771 101%	PASSED	98%	PASSED	95%	PASSED	104%	PASSED
FLEXURAL MODULUS, psi	562,800	LYPOED	649,337	PASSEU	644970	FASSED	767,237	FASSED
			U-2.33/		U443/U		#W#\C3/	



Worldwide Pipeline

17999 Edison Ave.

Tel: (636) 530-8000

Rehabilitation

Chesterfield, MO 63005

Fax: (636) 530-8744

102T Series
Polyester Resin
October 2014

Flexural Creep Testing for Gravity CIPP Applications

Insituform's 102T Series is a family of polyester resins for gravity sanitary and storm sewer applications. Resins currently approved for the 102T Series include:

AOC L758 Interplastic COR78-AT-559/5XX AOC L721 Insituform 102T

Typical Resin/Felt Properties

Flexural Strength, psi/MPa 4

4,500/31.5

ASTM D 790

Flexural Modulus, psi/MPa

500,000/2,760

ASTM D 790

Flexural Creep Testing

CIPP laminates made from each of Insituform's 102T Series resins were tested for flexural creep in accordance with ASTM D2990 for 10,000 hours.

Test Results

The results of tests for each group of laminates were plotted from 100 hours to 10,000 hours on a log/log graph, and a linear trend line was created. The 50 year flexural creep modulus was estimated by extending the linear regression to 50 years.

Safety

Safety guidelines are available in the appropriate Material Safety Data Sheet.

Detailed Information


Detailed information for any of the approved resins in the 102T Series can be provided upon request.

ASTM D 2990 Creep Modulus Data Insituform 102 T/TA Polyester Resin Insituform-102 Series Resin CENTRE for ADVANCEMENT of TRENCHLESS TECHNOLOGIES May 1, 2005

Elapsed Time	Flex Displ Avg (in)	Flex Creep Mod	Log Values		
(hours)		Avg (psi)	Time	Modulus	
1000	0.7240	593614	3.0000	5.7735	
3000	0.7767	552208	3.4771	5.7421	
6000	0.7920	541394	3.7782	5.7335	
10000	0.8350	512511	4.0000	5.7097	
438000		412000	5.6415	5.6149	
70000		412000	0.0410	 	

50-year projected creep modulus = 412,000 psi


Note: Data available in full report



ASTM D 2990 Creep Modulus Data AOC L721-LT Polyester Resin Insituform 102 Series Resin Microbac December 13, 2011

Elapsed Time	Flex Displ Avg (in)	Flex Creep Mod	Log Values		
(hours)		Avg (psi)	Time	Modulus	
100	0.4277	486685	2.0004	5.6872	
196	0.4268	472531	2.2911	5.6744	
335	0.4260	461658	2.5244	5.6643	
437	0.4254	453185	2.6404	5.6563	
1441	0.4231	423727	3.1586	5.6271	
2043	0.4220	411252	3.3102	5,6141	
2620	0.4211	401484	3.4183	5.6037	
3362	0,4203	393836	3.5266	5.5953	
4293	0.4195	385482	3.6328	5.5860	
4892	0.4190	380492	3.6895	5.5803	
5640	0.4185	375809	3.7513	5.5750	
6122	0.4182	373235	3.7869	5.5720	
6718	0.4180	371235	3.8272	5.5696	
7415	0.4175	367127	3.8701	5,5648	
8230	0.4171	363806	3.9154	5.5609	
9270	0.4168	360535	3.9671	5,5569	
9913	0.4166	359357	3.9962	5.5555	
10179	0.4165	358178	4.0077	5.5541	
438000		278,100	5.6415	5.4442	


50-year projected creep modulus = 278,100 psi



ASTM D 2990 Creep Modulus Data AOC L758-LTI Polyester Resin Insituform 102 Series Resin Hauser Laboratories Boulder, CO August 17, 2005

Elapsed Time	Displacement	Creep Modulus	Log Values		
(hours)	Avg (in)	Avg (psi)	Time	Modulus	
99	0.0290	584660	1.9948	5.7669	
197	0.0298	569260	2.2953	5.7553	
268	0.0303	560940	2.4285	5.7489	
500	0.0312	544620	2.6993	5.7361	
698	0.0318	533000	2.8440	5.7267	
1037	0.0325	522140	3.0157	5.7178	
1343	0.0932	510740	3.1281	5.7082	
2014	0.0339	500180	3.3040	5.6991	
2758	0.0346	489720	3.4406	5.6899	
3458	0.0352	482240	3.5388	5.6833	
4200	0.0356	476220	3.6233	5.6778	
4925	0.0360	471140	3.6924	5.6731	
5637	0.0363	467240	3.7510	5,6695	
6381	0.0367	462120	3.8049	5.6648	
7102	0.0369	459640	3.8514	5.6624	
7751	0.0371	457380	3.8894	5.6603	
8493	0.0372	456440	3.9291	5.6594	
9262	0.0373	454440	3.9667	5,6575	
10011	0.0375	452500	4.0005	5.6556	
438000		362300	5.6415	5.5591	

50-year projected creep modulus = 362,300 psi



ASTM D 2990 Creep Modulus Data Interplastic COR 78-AT-559/5XX Polyester Resin Insituform-102 Series Resin Interplastic Corporation Thermoset Resins Division

Test Reporting	Date	September	18, 2012
-----------------------	------	-----------	----------

Elapsed Time	Displacement	Creep Modulus	Log	/alues
(hours)	Avg (in)	Avg (psi)	Time	Modulus
100	no data	527400	2,0000	5.7221
196	available	516500	2.2923	5.7131
500		486900	2.6990	5.6874
700		474600	2.8451	5.6763
1004		463100	3.0017	5.6657
2012	20	443300	3.3036	5.6467
3019		433900	3.4799	5.6374
4028		424900	3.6051	5.6283
5036		422000	3.7021	5.6253
6044		420400	3.7813	5.6237
7052		414400	3.8483	5.6174
8059		409400	3,9063	5,6121
9000		402700	3.9542	5.6050
10003		397800	4,0001	5,5997
438000		320200	5.6415	5.5054

50-year projected creep modulus =

320,200

