



Scale: 3" = 1'-0"

FACILITIES


DRWN BY: SS
CKD BY: EAV
DATE: 07/2219


SCALE: AS NOTED

SHEET NO:

W.O. NUMBER 19*10427

EAV





Scale: 3" = 1'-0"



- SEE WALL TYPES

– DRYWALL CORNER

-BACKER ROD AND CAULK FULL PERIMETER BOTH SIDES, SHIM AS

— ALUMINUM DOOR FRAME WITH STOP -


FLUSH FRAME FACE TO

ACTIVE SIDE OF DOOR


NECESSARY


BEAD FULL PERIMETER, EACH SIDE TYP.













— SEALANT BOTH


Scale: 3" = 1'-0"

SIDES-TYP.





INTERIOR ALUM. - GLASS @ SILL
















HOLLOW METAL FRAME -

W/3 JAMB ANCHORS

SCHEDULED DOOR —


DOUBLE METAL STUDS -

& METAL STUD TRACK

PERIMETER SEAL


PEMKO #303APK —

OR EQUAL












FINISH FLOOR PLAN



LEGEND:

CPT1: MODULAR CARPET TILE - TYPICAL BBT1: BIO-BASED VINYL TILE 12X24 PT1: 12x24 PORCELAIN FLOOR TILE

1. CONTRACTOR SHALL REVIEW ALL SECTIONS OF THIS DOCUMENT AND NOTIFY PIMA COUNTY ANY DISCREPANCIES OR OMISSIONS.

CONC: SEALED CONCRETE

- FOR ANY ITEM REQUIRING A COLOR OR FINISH SELECTION THAT IS NOT INDICATED, CONTACT PIMA COUNTY.
- CHANGES IN FLOOR TYPES AT THE DOOR OPENING SHALL OCCUR AT THE CENTER OF THE DOOR FRAME UNLESS OTHERWISE NOTED.
- 4. CONTRACTOR SHALL CLEAN, PATCH AND REPAIR ALL SURFACES AND SUBSTRATES AS PER FINISH MATERIAL MANUFACTURER'S INSTALLATION REQUIREMENTS PRIOR TO INSTALLATION.
- 5. PROVIDE EPOXY GROUT AT ALL PORCELAIN TILE LOCATIONS.
- 6. WALL TILE LOCATIONS ARE INDICATED PER PLAN SEE RESTROOM ELEVATIONS AND TYPICAL TILE LAYOUT.
- PROVIDE 18" SQUARE AREA OF 'MOSAIC' FLOOR TILE CENTERED ON RESTROOM FLOOR DRAINS AND SLOPED TO THE DRAIN TO ASSIST WATER DRAINAGE. CREATE THE 'MOSAIC' TILE BY CUTTING THE 12" X 12" PORCELAIN FLOOR TILE INTO 2" X 2" MOSAIC.
- CONTRACTOR SHALL REVIEW ALL SECTIONS OF THIS DOCUMENT AND NOTIFY ARCHITECT OF ANY DISCREPANCIES OR OMISSIONS.
- 9. FOR ANY ITEM REQUIRING A COLOR OR FINISH SELECTION THAT IS NOT INDICATED, CONTACT ARCHITECT.

FINISH NOTES:


- 1. ELEVATOR WALL: PAINT ELEVATOR DOOR AND TRIM 'P2'. PAINT 'P1' ON REMAINING WALL SURFACE AT ELEVATORS.
- FIELD PAINT COLOR IS 'P1'. ACCENT PAINT COLORS ARE 'P2, P3, P4, P5 AND P6', UNLESS OTHERWISE NOTED.
- 3. STAIRWELL DOORS: PAINT DOOR AND TRIM 'P2'.
- 4. SOFFIT ACCENT PAINT: PAINT SOFFIT AREAS IN LOBBY AND CONFERENCE ROOM TO BE PAINTED 'P4'. PAINT BOTTOM AND ALL VERTICAL SIDES OF SOFFIT, INCLUDING SOFFIT FACE TO 10' A.F.F. AT CLOUD' CEILINGS AS SHOWN ON REFLECTED CEILING PLAN.
- PAINT ALL OPEN AREAS AND 'CLOUD' CEILING AREAS 'FLAT BLACK' (P8) ABOVE 10' A.F.F.
- PROVIDE WINDOW COVERING 'RS1' AT ALL EXTERIOR WINDOWS EXCEPT MEN'S RM. PROVIDE SINGLE WIDTH SHADES UNLESS WIDTH EXCEEDS 144". IF WIDTH EXCEEDS 144" PROVIDE SINGLE SHADE MOUNTING SYSTEM FOR MULTIPLE WIDTHS, DIVIDE WIDTHS USING EXISTING BUILDING MULLIONS.
- 7. ALL GWB CEILINGS, HEADERS AND SOFFITS TO BE PAINTED 'P1' UNLESS OTHERWISE NOTED (SEE ADDITIONAL DIRECTION IN NOTE 4).

WINDOW COVERING NOTES:

- 1. PROVIDE WINDOW COVERING 'RS1' AT ALL EXTERIOR WINDOWS EXCEPT MEN'S RM. PROVIDE SINGLE WIDTH SHADES UNLESS WIDTH EXCEEDS 144". IF WIDTH EXCEEDS 144" PROVIDE SINGLE SHADE MOUNTING SYSTEM FOR MULTIPLE WIDTHS, DIVIDE WIDTHS USING EXISTING BUILDING MULLIONS.
- PROVIDE WINDOW COVERINGS 'RS2' AT ALL EAST AND NORTH EXTERIOR WINDOWS. PROVIDE SINGLE WIDTH SHADES UNLESS WIDTH EXCEEDS 144". IF WIDTH EXCEEDS 144" DIVIDE WIDTHS USING EXISTING BUILDING MULLIONS WITH LEAST AMOUNT OF SHADES POSSIBLE.

 $\overline{}$

ADMINIS



CKD BY: EAV DATE: 07/22/19 AS NOTED SCALE: SHEET NO:

W.O. NUMBER 19*10427